

BOQ for Glass House Construction in Old and New Building

SL #	BSR 2021	DESCRIPTION OF ITEMS OF WORK	QUANTITY	UNIT	Rate (Nu)
1	WW0055	Providing & fixing Class 'B' (conifer) (undressed) in wall frames etc	0.986	cu.m	
2	WW0061	Providing & fixing roof framing, in trusses, purlins, rafters, posts, post plates including hoisting, etc. (excluding steel items)	1.708	cu.m	
3	-	Glass Panel (12mm)	41.178	sq.m	
4	RF0003	Providing & fixing Pre Painted Steel Corrugated Roofing sheets, including bolts, hooks and nuts 8mm dia. with bitumen and G.I limpet washers filled with white lead for connection, excluding the cost of purlins, rafter and trusses.	45.815	sq.m	
5	WW0130	Providing & fixing Plywood lining with necessary nails etc. including beading complete (excluding cost of frame)	43.402	sq.m	
6	SW0045	Providing & fixing anodised Aluminium section for doors, windows, ventilators, partitions framing, false ceiling framing of specified sections including all accessories such as U-rubber gasket for fixing glass panes, weather strips or weather seals, roller, springs, etc complete (excluding the cost of glass panes or boards in case of partitions/doors/windows and ceiling boards in case of ceiling)	18.237	Kg	
7	RF0010	Providing & fixing 450mm over all semi-circular plain G.I gutter, including brackets, bolts, nuts, washers & rain water pipes connections, excluding the cost of pipes	27.000	m	
				Total (Nu)	

In words.....